





1



 BB =
 Closed-fronted bird boxes need to be placed away

 From direct sunlight and prevailing winds, so facing

 between east and north is ideal. Ensure that entrances

 to the boxes are not impeded by vegetation, wires etc.

 Boxes need to be a minimum of 1.5m from the ground.

 ONE BOX TO BE ADDED TO EACH GABLE END OF

 BUILDING.

±

Schedule of Finishes			
ltem	Туре	Colour	
Ridge tiles	Dry Vented clay	Blue/black	
Roof	Synthetic slate & zinc profile	Blue/black	
Facia & soffits	UPVC	TBD	
Gutters	UPVC	TBD	
Down-pipes	UPVC	TBD	
Walls	Smooth texture cement render, with stone work or similar where indicated	Textured cement tbc	
Front and back door	UPVC	TBD	
Windows	UPVC	TBD	
Window cills	Natural slate	Blue/black	

PL VER 1	10/05/24	All measurements must be checked on site. If there are any deviations the designer should be notified and written conformation sought.			
		The plans are the property of M. Baggott Chartered Surveyors and Architectural Service and written permission must be sought before passing any plans onto third parties.			
		Party Wall agreements should be put in place before any works commence on site.			
No.	Date	Issue Notes			
1	MARK BAGGOTT CHARTERED				
	ARCHITECTURAL PRACTICE				
Consulta	p. 01559371550 m. 07717292879 e. mark@baggottmark.co.uk				
Project 1	Project Title				
	Proposed development of 'Block 1' at former secondary school, Llandysul, Ceredigion.				
	Sheet Title PROPOSED ELEVATIONS AND FLOOR PLANS				
Project N	Manager N/A	Project ID BLOCK 1			
Drawn B	^{yy} MB	Scale 1:100; 1:50;			
Reviewe	ed By	Sheet No.			
Date	19/04/20	024			
	CAD File Name PAPER A1				